



ABSTRACT OF QUOTATION
SOLICITATION Number: RSU-75-18
ABC: PhP447,845.00
QTY: 523.5

PROCUREMENT OF VARIOUS CONSTRUCTION MATERIALS & SUPPLIES (REPOST)

LOT-2: CEILING WORKS (ABC: PhP339,625.00, QTY: 522.5)

LOT-3: FIRE ESCAPE W/ INSTALLATION (PhP108,220.00, QTY: 1)

LOT-2: CEILING WORKS (ABC: PhP339,625.00, QTY: 522.5)

UNIT	ITEM DESCRIPTION	QTY	ESTIMATED UNIT COST	ESTIMATED COST
Sq.m	Hardiflex Ceiling 1/4" with Aluminum frame and Air Ventilation with Installation	522.5		
TOTAL	QTY	522.5	ESTIMATED COST	

LOT-3: FIRE ESCAPE W/ INSTALLATION

UNIT	ITEM DESCRIPTION	QTY	ESTIMATED UNIT COST	ESTIMATED COST
lot	Fire Escape w/Installation: 8mm Steel Channel, Stair Threads; 6mm thick Checkered Plate; 4" Sched.40 Pipe Column; C8 x 13 landing support 4.5mm x 65mm x 65mm Angle bar, 8mm thick 0.15 x 0.15 base plate with 4-12mm dia. Anchor bolts and Washers, 10mm x 75mm x 150mm Gusset Plate, 12mm Blind Flange with Spider Leg; C8 x 13 Stringer; 25 x 25 x 4.5 mm thick Angle Bar; 38 x 38 x 4.5mm thick x 200mm long seat angle; 12 mm thick x 100 wide x 200 long w/12mm dia. Anchor B; Welding Rod; 50mm x 50mm x 4.5mm thick Angle bar; Acetylene, Oxygen Tank, Misc. Materials.	1		
TOTAL	QTY	1	ESTIMATED COST	