



**TECHNICAL SPECIFICATIONS**  
**SOLICITATION Number RSU-75-18**  
**ABC: PhP447,845.00**  
**QTY: 523.5**

**PROCUREMENT OF VARIOUS CONSTRUCTION MATERIALS & SUPPLIES (REPOST)**

**LOT-2: CEILING WORKS (ABC: PhP339,625.00, QTY: 522.5)**

**LOT-3: FIRE ESCAPE W/ INSTALLATION (PhP108,220.00, QTY: 1)**

**LOT-2: CEILING WORKS (ABC: PhP339,625.00, QTY: 522.5)**

UNIT	ITEM DESCRIPTION	STATEMENT OF COMPLIANCE
Sq.m	<b>Hardeflix Ceiling 1/4"</b> with Aluminum frame and Air Ventilation with Installation	

**LOT-3: FIRE ESCAPE W/ INSTALLATION (PhP108,220.00, QTY: 1)**

UNIT	ITEM DESCRIPTION	STATEMENT OF COMPLIANCE
lot	<b>Fire Escape w/Installation:</b> 8mm Steel Channel, Stair Threads; 6mm thick Checkered Plate; 4" Sched.40 Pipe Column; C8 x 13 landing support 4.5mm x 65mm x 65mm Angle bar, 8mm thick 0.15 x 0.15 base plate with 4-12mm dia. Anchor bolts and Washers, 10mm x 75mm x 150mm Gusset Plate, 12mm Blind Flange with Spider Leg; C8 x 13 Stringer; 25 x 25 x 4.5 mm thick Angle Bar; 38 x 38 x 4.5mm thick x 200mm long seat angle; 12 mm thick x 100 wide x 200 long w/12mm dia. Anchor B; Welding Rod; 50mm x 50mm x 4.5mm thick Angle bar; Acetylene, Oxygen Tank, Misc. Materials.	1