



# ROMBLON STATE UNIVERSITY

## BIDS AND AWARDS COMMITTEE

Community Outreach Center, RSU-Main Campus, Liwanag, Odiongan, Romblon 5505  
Telephone: (042) 567-5952  
Email: bac@rsu.edu.ph  
Website: rsu.edu.ph



## ***SPECIFICATIONS***

The Repair and Rehabilitation of the University Hostel Phase 2 will be located at RSU Main Campus, Brgy. Liwanag, Odiongan, Romblon, The following are the description of works to be done:

### **I. Windows Works and Steel Front Design Works with installation**

- a. Remove and replace of 6mm thick tinted Green Glass Sliding Window with 2 Inches x 4 inches Analoc frame powder coated Green (Size:1.5m x 1.67m);
- b. Remove and replace of 6mm thick tinted Green Glass Sliding Window with 2 Inches x 4 inches Analoc frame powder coated Green (Size:0.70m x 1.3m);
- c. Remove ng Replace of Broken Glass of Sliding Glass Window Size: 1.5m x 1.25m;
- d. Remove and Replace of all front windows to 6mm thick tinted brown glass with 2" x 4" Analoc Frame powder coated Brown Finish, Dimensions:  
3m x 1.5m – 3 Sets, 2m x 1.4m – 1 Set, 1.6m x 1.5m – 1 Set, 1.6m x 1.4m – 1 Set, .5m x 1.4m – 2 Sets, .6m x 0.5m – 2 sets;
- e. Fabrication and Installation of Steel Front Wind Breaker Designs Using 1 inch x 2 inches x 1.2mm thick Steel Tubular in Brown Painted Finish, Dimensions:  
12.1mL x 3.2mH;
- f. Dismantling and Repair of Front Windows (1.7m x .5m); and
- g. Relocation of Rear window for Provision of Fire exit stairs.

### **II. Stainless Railings and Stainless Metal Plates Works**

- a. Buffing of Stainless railing on 2 inches diameter SUS 304 Stainless Pipe and Fabrication of Stainless Metal Plates "HOSTEL" 0.4mH x 0.3mL

### **III. Painting and Repainting Works**

- a. The painting and repainting works has a total area of 2,691.6 Sq.m compose of Flat Latex, Semi Gloss Latex White Paint, Gloss Caramel Brown Paint, Flat Black Paint.

### **IV. Air Conditioning Units with Installation**

- a. Installation of twenty (20) Set 2.5Hp window type air conditioning unit with complete accessories

The project can be completed within **60 Calendar Days**. The Total estimated cost of the project is **Two Million, Three Hundred Thirty-Two Thousand, Two Hundred Pesos Only (PhP2,332,200.00)**.